

2nd Floor Quoting Format and Specifications

	Description	Unit	Amount
1.00	Dividing Wall		
1.01	SUPPLY AND CONSTRUCTION OF 2 (TWO) FACED WALL MADE OUT OF FIRE RATED TBR 5/8" (16MM) SHEETS, GAUGE 20 USG GALV. STEEL STUDS AND GAUGE 20 USG GALV. STEEL CEILING AND FLOOR RUNNERS, @ 40CM APART TO BUILD A 6" THICK WALL, 2" ACOUSTIC GLASS FIBER INSULATION OR MINERAL FIBER (AISLHOGAR), TAPE -ON PAPER-FACED METAL CORNER BEAD (INSIDE AND OUTSIDE PROFILES), JOINT TAPE, ETC. WALL FROM FLOOR TO 3 M HIGH.	m ²	54.75
1.02	SUPPLY AND APPLICATION OF VINYL PAINT ON WALLS, BRAND: BENJAMIN MOORE, LINE: ECO SPEC EGGSHELL, COLOR BARBADOS SAND 1094. IT INCLUDES ONE COAT OF BENAJMIN MOORE SEALER AND AT LEAST TWO COATS OF PAINT. IT INCLUDES: PLASTERING, SANDING AND ALL THE NECESSARY LABOR AND MATERIAL TO PERFORM THE WORK.	m ²	109.50
1.03	SUPPLY OF WATER BASED CARPET TILE ADHESIVE AND INSTALLATION OF GOVERNMENT FURNISHED CARPET TILE TO REPAIR AROUND WALL INSTALLATION. IT INCLUDES CLEANING THE FLOOR, CUTTINGS, OVERAGE, ETC. TO PROPERLY PERFORM WORK.	ml	15.00
1.04	SUPPLY AND INSTALLATION OF BROWN 4" HIGH VINYL BASE BOARD, 3 MM THICK EXPORT QUALITY, BRAND VINYLASA (NO GLOSS FINISH) OR EQUIVALENT. IT INCLUDES ALL THE NECESSARY MATERIALS AND TOOLS TO PERFORM WORK.	ml	30.00
1.05	ADJUSTMENT OF DROP CEILING DUE TO WALL INSTALLATION, INCLUDING ANY MATERIALS NECESSARY TO MATCH EXISTING INSTALLATION.	ml	15.00
1.06	SUPPLY AND INSTALLATION OF ELECTRICAL OUTLET INSIDE WALL. IT INCLUDES: 3/4" THICK WALL CONDUIT, POLARIZED OUTLETS, BRAND: TWO LEVITON CR20-I COMMERCIAL DUPLEX, 20 AMPS, 125 VOLTS PER DROP, COLOR IVORY; LEVITON 2 GANG DUPLEX STAINLESS STEEL RECEPTACLE COVER PLATE, CONDUMEX # 10 WIRE, CONDUMEX INSULATED GREEN COLORED GROUND WIRE # 12, PLASTIC END CAPS AND TAPE, STAMP CIRCUIT NUMBER ON FACE PLATE (AS IN THE REST OF THE SPACE) AND ALL THE NECESSARY MATERIAL AND LABOR FOR A PROPER INSTALLATION. USE EXSITING CIRCUITS TO BE ASSIGNED BY POST.	sal	2.00
2.00	Break Room		
2.01	SUPPLY AND CONSTRUCTION OF 2 (TWO) FACED WALL MADE OUT OF FIRE RATED TBR 5/8" (16MM) SHEETS, GAUGE 20 USG GALV. STEEL STUDS AND GAUGE 20 USG GALV. STEEL CEILING AND FLOOR RUNNERS, @ 40CM APART TO BUILD A 6" THICK WALL, 2" ACOUSTIC GLASS FIBER INSULATION OR MINERAL FIBER (AISLHOGAR), TAPE -ON PAPER-FACED METAL CORNER BEAD (INSIDE AND OUTSIDE PROFILES), JOINT TAPE, ETC. WALL FROM FLOOR TO 3 M HIGH. IT INCLUDES WOODEN SUPPORTS AROUND THE DOOR AND WINDOW'S OPENINGS (SIZE TO FILL THE METAL STUDS, APROX. 3" X 2") FOR NEW DOOR/WINDOW FRAMES TO BE INSTALLED, AND ALL NESSARY MATERIALS TO PERFORM THE WORK ACCORDING TO THE MANUFACTURER..	m ²	34.12
2.02	SUPPLY AND APPLICATION OF VINYL PAINT ON WALLS, BRAND: BENJAMIN MOORE, LINE: ECO SPEC EGGSHELL, COLOR BARBADOS SAND 1094. IT INCLUDES ONE COAT OF BENAJMIN MOORE SEALER AND AT LEAST TWO COATS OF PAINT. IT INCLUDES: PLASTERING, SANDING AND ALL THE NECESSARY LABOR AND MATERIAL TO PERFORM THE WORK.	m ²	68.24
2.03	SUPPLY AND INSTALLATION OF BROWN 4" HIGH VINYL BASE BOARD, 3 MM THICK EXPORT QUALITY, BRAND VINYLASA (NO GLOSS FINISH) OR EQUIVALENT. IT INCLUDES ALL THE NECESSARY MATERIALS AND TOOLS TO PERFORM WORK.	ml	18.66
2.04	ADJUSTMENT OF DROP CEILING DUE TO WALL INSTALLATION, INCLUDING ANY MATERIALS NECESSARY TO MATCH EXISTING INSTALLATION.	ml	1.00
2.05	ADJUSTMENT OF ONE FIRE SPRINKLER AS PER PLANS, SPRINKLER TECHNICIAN QUALIFIED PER DOS SPECIFICATIONS.	pc	1.00

2.06	SUPPLY AND INSTALLATION OF ELECTRICAL OUTLET INSIDE WALL. IT INCLUDES: 3/4" THICK WALL CONDUIT, POLARIZED OUTLETS, BRAND: TWO LEVITON GFCI CR20-I COMMERCIAL DUPLEX, 20 AMPS, 125 VOLTS PER DROP, COLOR IVORY; LEVITON 2 GANG DUPLEX STAINLESS STEEL RECEPTACLE COVER PLATE, CONDUMEX # 10 WIRE, CONDUMEX INSULATED GREEN COLORED GROUND WIRE # 12, PLASTIC END CAPS AND TAPE, STAMP CIRCUIT NUMBER ON FACE PLATE (AS IN THE REST OF THE SPACE) AND ALL THE NECESSARY MATERIAL AND LABOR FOR A PROPER INSTALLATION. USE EXSITING CIRCUITS TO BE ASSIGNED BY POST.	sal	2.00
2.07	SUPPLY AND INSTALLATION OF TRIPLE TOGGLE LIGHT SWITCH AND THE CONNECTION OF THE LAMPS TO IT. BRAND: TOGGLE SWITCH LEVITON, CS220-21, COLOR IVORY, STAINLESS STEEL FACE PLATE, LEVITON 84009 2 GANG STAINLESS STEEL TOGGLE SWITCH WALL PLATE, JUNCTION BOXES, THICK WALL CONDUIT, CONDUMEX CABLE # 12, CONDUMEX INSULATED GREEN COLORED GROUND WIRE # 12, PLASTIC END CAPS AND TAPE, CONNECTORS, BRACES, AND ALL THE NECESSARY MATERIAL TO DO THE WORK.	sal	1.00
2.08	SUPPLY AND INSTALLATION OF NEW CABINETRY, PLASTIC COUNTERTOP LAMINATE FINISH AND ABS END MOULDING, MDF LUMBER, SIZE 1844 mm WIDE X 864 mm HEIGHT AND 654 mm DEPTH., CONCEALED HINGES BRAND BLOOM, MORTISE PRIMELINE SPRING LOADED DRWER END CABINET LOCK MOD. U10665. TO INCLUDE UPPER AND LOWER CABINETS SIZED PER THE PLANS. SUPPLY AN INSTALATION OF SINK TO INCLUDE PLUMBING. SINK SHOULD BE SIMILAR MAKE AND MODEL TO EXISTING SINKS. DRAINAGE PIPE SHOULD BE 2" PVC AND SUPPLY WILL BE 3/4" COPPER PIPES WELDED AT THE CONNECTIONS.	pc	1.00
3.00	Conference Room		
3.01	SUPPLY AND CONSTRUCTION OF 2 (TWO) FACED WALL MADE OUT OF FIRE RATED TBR 5/8" (16MM) SHEETS, GAUGE 20 USG GALV. STEEL STUDS AND GAUGE 20 USG GALV. STEEL CEILING AND FLOOR RUNNERS, @ 40CM APART TO BUILD A 6" THICK WALL, 2" ACOUSTIC GLASS FIBER INSULATION OR MINERAL FIBER (AISLHOGAR), TAPE -ON PAPER-FACED METAL CORNER BEAD (INSIDE AND OUTSIDE PROFILES), JOINT TAPE, ETC. WALL FROM FLOOR TO 3 M HIGH. IT INCLUDES WOODEN SUPPORTS AROUND THE DOOR AND WINDOW'S OPENINGS (SIZE TO FILL THE METAL STUDS, APROX. 3" X 2") FOR NEW DOOR/WINDOW FRAMES TO BE INSTALLED, AND ALL NESSARY MATERIALS TO PERFORM THE WORK ACCORDING TO THE MANUFACTURER. I	m ²	88.29
3.02	SUPPLY AND APPLICATION OF VINYL PAINT ON WALLS, BRAND: BENJAMIN MOORE, LINE: ECO SPEC EGGSHELL, COLOR BARBADOS SAND 1094. IT INCLUDES ONE COAT OF BENAJMIN MOORE SEALER AND AT LEAST TWO COATS OF PAINT. IT INCLUDES: PLASTERING, SANDING AND ALL THE NECESSARY LABOR AND MATERIAL TO PERFORM THE WORK.	m ²	176.58
3.03	SUPPLY AND INSTALLATION OF BROWN 4" HIGH VINYL BASE BOARD, 3 MM THICK EXPORT QUALITY, BRAND VINYLASA (NO GLOSS FINISH) OR EQUIVALENT. IT INCLUDES ALL THE NECESSARY MATERIALS AND TOOLS TO PERFORM WORK.	ml	48.38
3.04	SUPPLY OF WATER BASED CARPET TILE ADHESIVE AND INSTALLATION OF GOVERNMENT FURNISHED CARPET TILE TO REPAIR AROUND WALL INSTALLATION. IT INCLUDES CLEANING THE FLOOR, CUTTINGS, OVERAGE, ETC. TO PROPERLY PERFORM WORK.	ml	24.18
3.05	SUPPLY AND INSTALLATION OF A DOOR FRAME. BRAND: MPI (METAL PRODUCTS INC.) OR EQUIVALENT. FRAMES OF HOT OR COLD ROLLED STEEL, FABRICATED FRAMES OF FULL-WELDED UNIT CONSTRUCTION, WITH CORNERS MITERED, REINFORCED, AND CONTINUOUSLY WELDED FULL WIDTH OF MITRE. KNOCKDOWN FRAME ARE ACCEPTABLE FOR DRYWALL CONSTRUCTION. THICKNESS: 1.9 MM. JAMB ANCHORS: INSERT TYPE WITH NOTCHED CLIP TO ENGAGE METAL STUD, WELDED TO BACK OF FRAMES, FORMED OF SAME MATERIAL AS FRAME, NOT LESS THAN 1.0 MM THICK 4 ANCHORS PER JAMB. INSTALL GOVERNMENT FURNISHED DOOR TO FRAME.	pc	1.00
3.06	ADJUSTMENT OF DROP CEILING DUE TO WALL INSTALLATION, INCLUDING ANY MATERIALS NECESSARY	ml	48.38

3.08	SUPPLY AND INSTALLATION OF ELECTRICAL OUTLET INSIDE WALL. IT INCLUDES: 3/4" THICK WALL CONDUIT, POLARIZED OUTLETS, BRAND: TWO LEVITON CR20-I COMMERCIAL DUPLEX, 20 AMPS, 125 VOLTS PER DROP, COLOR IVORY; LEVITON 2 GANG DUPLEX STAINLESS STEEL RECEPTACLE COVER PLATE, CONDUMEX # 10 WIRE, CONDUMEX INSULATED GREEN COLORED GROUND WIRE # 12, PLASTIC END CAPS AND TAPE, STAMP CIRCUIT NUMBER ON FACE PLATE (AS IN THE REST OF THE SPACE) AND ALL THE NECESSARY MATERIAL AND LABOR FOR A PROPER INSTALLATION. USE EXSITING CIRCUITS TO BE ASSIGNED BY POST.	sal	5.00
3.09	SUPPLY AND INSTALLATION OF TRIPLE TOGGLE LIGHT SWITCH AND THE CONNECTION OF THE LAMPS TO IT. BRAND: TOGGLE SWITCH LEVITON, CS220-21, COLOR IVORY, STAINLESS STEEL FACE PLATE, LEVITON 84009 2 GANG STAINLESS STEEL TOGGLE SWITCH WALL PLATE, JUNCTION BOXES, THICK WALL CONDUIT, CONDUMEX CABLE # 12, CONDUMEX INSULATED GREEN COLORED GROUND WIRE # 12, PLASTIC END CAPS AND TAPE, CONNECTORS, BRACES, AND ALL THE NECESSARY MATERIAL TO DO THE WORK.	sal	2.00
3.10	SUPPLY AND INSTALLATION OF VOICE - DATA DROPS AND OUTLET IN WALL FOR THE PRIVATE OFFICE WITH THE SAME SPECS AS EXISTING IN THE OTHER OFFICES IN THE AREA. IT INCLUDES: 1" THICK WALL CONDUIT FROM THE TRAY, JUNCTION BOXES, PULL STRING, BRACING, 2 BLUE BELDEN COPPER MEDIA TWIST CMR CAT:6 CABLE FOR DATA, 1 GREY BELDEN COPPER MEDIA CAT:5e CABLE FOR TELEPHONE, 2 BELDEN RJ-45 JACKS CAT 6 (1 ORANGE, 1 GREEN), BELDEN RJ-45 CAT 5:e (BLUE), 2 BELDEN RJ-45 TELEPHONE JACKS IVORY (AS SHOWN IN PHOTO), 2 AND 4 PORTS MDVO BELDEN DOUBLE TOGGLE ANGLE ENTRY FACE PLATE, DUST COVER TO ALL PORTS, MODULAR JACKS AND ADAPTERS AT THE FACE PLATE, WHITE, RJ-45 CAT -6 AND CAT 5e PLUGS. IDENTIFICATION OF EACH CABLE ON BOTH ENDS, PUNCHING CABLE TO JACKS AND TO PLUGS AND ALL THE NECESSARY MATERIAL FOR A PROPER INSTALLATION. RUN CABLES TO TELEPHONE AND DATA CLOSETS WITHIN THE AREA (SEE PHOTO ENCLOSED IN SPECS).	sal	2.00
4.00	Private Office		
4.01	SUPPLY AND CONSTRUCTION OF 2 (TWO) FACED WALL MADE OUT OF FIRE RATED TBR 5/8" (16MM) SHEETS, GAUGE 20 USG GALV. STEEL STUDS AND GAUGE 20 USG GALV. STEEL CEILING AND FLOOR RUNNERS, @ 40CM APART TO BUILD A 6" THICK WALL, 2" ACOUSTIC GLASS FIBER INSULATION OR MINERAL FIBER (AISLHOGAR), TAPE -ON PAPER-FACED METAL CORNER BEAD (INSIDE AND OUTSIDE PROFILES), JOINT TAPE, ETC. WALL FROM FLOOR TO 3 M HIGH. IT INCLUDES WOODEN SUPPORTS AROUND THE DOOR AND WINDOW'S OPENINGS (SIZE TO FILL THE METAL STUDS, APROX. 3" X 2") FOR NEW DOOR/WINDOW FRAMES TO BE INSTALLED, AND ALL NESSARY MATERIALS TO PERFORM THE WORK ACCORDING TO THE MANUFACTURER..	m ²	27.19
4.02	SUPPLY AND APPLICATION OF VINYL PAINT ON WALLS, BRAND: BENJAMIN MOORE, LINE: ECO SPEC EGGSHELL, COLOR BARBADOS SAND 1094. IT INCLUDES ONE COAT OF BENAJMIN MOORE SEALER AND AT LEAST TWO COATS OF PAINT. IT INCLUDES: PLASTERING, SANDING AND ALL THE NECESSARY LABOR AND MATERIAL TO PERFORM THE WORK.	m ²	54.38
4.03	SUPPLY AND INSTALLATION OF BROWN 4" HIGH VINYL BASE BOARD, 3 MM THICK EXPORT QUALITY, BRAND VINYLASA (NO GLOSS FINISH) OR EQUIVALENT. IT INCLUDES ALL THE NECESSARY MATERIALS AND TOOLS TO PERFORM WORK.	ml	14.90
4.04	SUPPLY OF WATER BASED CARPET TILE ADHESIVE AND INSTALLATION OF GOVERNMENT FURNISHED CARPET TILE TO REPAIR AROUND WALL INSTALLATION. IT INCLUDES CLEANING THE FLOOR, CUTTINGS, OVERAGE, ETC. TO PROPERLY PERFORM WORK.	ml	7.45
4.05	SUPPLY AND INSTALLATION OF A DOOR FRAME. BRAND: MPI (METAL PRODUCTS INC.) OR EQUIVALENT. FRAMES OF HOT OR COLD ROLLED STEEL, FABRICATED FRAMES OF FULL-WELDED UNIT CONSTRUCTION, WITH CORNERS MITERED, REINFORCED, AND CONTINUOSLY WELDED FULL WIDTH OF MITRE. KNOCKDOWN FRAME ARE ACCEPTABLE FOR DRYWALL CONSTRUCTION. THICKNESS: 1.9 MM. JAMB ANCHORS: INSERT TYPE WITH NOTCHED CLIP TO ENGAGE METAL STUD, WELDED TO BACK OF FRAMES, FORMED OF SAME MATERIAL AS FRAME, NOT LESS THAN 1.0 MM THICK 4 ANCHORS PER JAMB. INSTALL GOVERNMENT FURNISHED DOOR TO FRAME.	pc	1.00
4.06	ADJUSTMENT OF DROP CEILING DUE TO WALL INSTALLATION, INCLUDING ANY MATERIALS NECESSARY TO MATCH EXISTING INSTALLATION.	ml	14.90

4.08	SUPPLY AND INSTALLATION OF ELECTRICAL OUTLET INSIDE WALL. IT INCLUDES: 3/4" THICK WALL CONDUIT, POLARIZED OUTLETS, BRAND: TWO LEVITON CR20-I COMMERCIAL DUPLEX, 20 AMPS, 125 VOLTS PER DROP, COLOR IVORY; LEVITON 2 GANG DUPLEX STAINLESS STEEL RECEPTACLE COVER PLATE, CONDUMEX # 10 WIRE, CONDUMEX INSULATED GREEN COLORED GROUND WIRE # 12, PLASTIC END CAPS AND TAPE, STAMP CIRCUIT NUMBER ON FACE PLATE (AS IN THE REST OF THE SPACE) AND ALL THE NECESSARY MATERIAL AND LABOR FOR A PROPER INSTALLATION. USE EXSITING CIRCUITS TO BE ASSIGNED BY POST.	sal	5.00
4.09	SUPPLY AND INSTALLATION OF TRIPLE TOGGLE LIGHT SWITCH AND THE CONNECTION OF THE LAMPS TO IT. BRAND: TOGGLE SWITCH LEVITON, CS220-21, COLOR IVORY, STAINLESS STEEL FACE PLATE, LEVITON 84009 2 GANG STAINLESS STEEL TOGGLE SWITCH WALL PLATE, JUNCTION BOXES, THICK WALL CONDUIT, CONDUMEX CABLE # 12, CONDUMEX INSULATED GREEN COLORED GROUND WIRE # 12, PLASTIC END CAPS AND TAPE, CONNECTORS, BRACES, AND ALL THE NECESSARY MATERIAL TO DO THE WORK.	sal	1.00
4.10	SUPPLY AND INSTALLATION OF VOICE - DATA DROPS AND OUTLET IN WALL FOR THE PRIVATE OFFICE WITH THE SAME SPECS AS EXISTING IN THE OTHER OFFICES IN THE AREA. IT INCLUDES: 1" THICK WALL CONDUIT FROM THE TRAY, JUNCTION BOXES, PULL STRING, BRACING, REROUTING OF 2 BLUE CAT:6 CABLE FOR DATA, 1 GREY CAT:5e CABLE FOR TELEPHONE, 2 BELDEN RJ-45 JACKS CAT 6 (1 ORANGE, 1 GREEN), BELDEN RJ-45 CAT 5:e (BLUE), 2 BELDEN RJ-45 TELEPHONE JACKS IVORY, 2 AND 4 PORTS MDVO BELDEN DOUBLE TOGGLE ANGLE ENTRY FACE PLATE, DUST COVER TO ALL PORTS, MODULAR JACKS AND ADAPTERS AT THE FACE PLATE, WHITE, RJ-45 CAT -6 AND CAT 5e PLUGS.	sal	2.00
5.00	Teller Window and 3rd Floor Office		
5.01	REMOVAL OF EXISTING TELLER WINDOW IN THE CASHIER OFFICE AND RELOCATION/REINSTALLATION DOWNSTAIRS TO AN EXISTING OFFICE	pc	1.00
5.02	RELOCATION OF EXISTING OFFICE DOOR TO THE VACANT WINDOW SPACE.	pc	1.00
5.03	SUPPLY AND CONSTRUCTION OF 2 (TWO) FACED WALL MADE OUT OF FIRE RATED TBR 5/8" (16MM) SHEETS, GAUGE 20 USG GALV. STEEL STUDS AND GAUGE 20 USG GALV. STEEL CEILING AND FLOOR RUNNERS, @ 40CM APART TO BUILD A 6" THICK WALL, 2" ACOUSTIC GLASS FIBER INSULATION OR MINERAL FIBER (AISLHOGAR), TAPE -ON PAPER-FACED METAL CORNER BEAD (INSIDE AND OUTSIDE PROFILES), JOINT TAPE, ETC. WALL FROM FLOOR TO 3 M HIGH. IT INCLUDES WOODEN SUPPORTS AROUND THE DOOR AND WINDOW'S OPENINGS (SIZE TO FILL THE METAL STUDS, APROX. 3" X 2") FOR NEW DOOR/WINDOW FRAMES TO BE INSTALLED, AND ALL NESSARY MATERIALS TO PERFORM THE WORK ACCORDING TO THE MANUFACTURER..	m ²	5.00
5.04	SUPPLY AND APPLICATION OF VINYL PAINT ON WALLS, BRAND: BENJAMIN MOORE, LINE: ECO SPEC EGGSHELL, COLOR BARBADOS SAND 1094. IT INCLUDES ONE COAT OF BENAJMIN MOORE SEALER AND AT LEAST TWO COATS OF PAINT. IT INCLUDES: PLASTERING, SANDING AND ALL THE NECESSARY LABOR AND MATERIAL TO PERFORM THE WORK.	m ²	10.00
5.05	SUPPLY AND INSTALLATION OF BROWN 4" HIGH VINYL BASE BOARD, 3 MM THICK EXPORT QUALITY, BRAND VINYLASA (NO GLOSS FINISH) OR EQUIVALENT. IT INCLUDES ALL THE NECESSARY MATERIALS AND TOOLS TO PERFORM WORK.	ml	3.00
	SUBTOTAL		
	V.A.T. 16%		
	ESTIMATE TOTAL		TOTAL I

	0.00	
	0.00	
	0.00	
		0.00
	0.00	
	0.00	
	0.00	
	0.00	
	0.00	
		0.00
	SUB TOTAL	0.00
	I.V.A.	0.00
	DEL PRESUPUESTO	0.00